Classic Log Homes, Inc.

SAMPLE PURCHASE

Barton 26 x34 Cabin w/ Double Round Logs

Jeff Glaza
3981 Pryne Road
Wisconsin Rapids, WI 54495
Phone: 715-887-2550
E-mail: jeff@classicloghomes.biz
Web: www.classicloghomes.biz

PROPOSAL DATE: July 17, 2011

Proposal Submitted to:

Job Address:

26 x34 Cabin w/ Double Round Logs

Description	Lineal Foot	Price per LF	AMOUNT
8" stack x 11" average thickness Natural Double-Round double-peeled for walls and gables			
2220	2220	$6.98	$15,495.60
8" stack x 13" average thickness Natural Double-Round (for gables vertical and rake log)			
4-18'	72	$8.78	$632.16
2-12'	24	$8.78	$210.72
8" stack x 6" thick rough-sawn square logs for interior loft bearing walls			
9-8'	72	$3.38	$243.36
2-10'	20	$3.38	$67.60
3-12'	36	$3.38	$121.68
14-14'	196	$3.38	$662.48
8" x 8" square log rough-sawn log loft floor joist			
4-16'	64	$4.28	$273.92
5-20' (8" x 10")	100	$5.99	$599.00
9" top log collar ties or (cross ties)			
2-28'	56	$9.00	$504.00
14" top Ridge log for 4' gable overhangs			
1-24'	24	$12.00	$288.00
1-20'	20	$9.75	$195.00
2"x8" T&G flooring			
900 lf	900	$1.00	$900.00
8" top Log posts			
2-8'	16	$3.83	$61.28
1-12'	12	$3.83	$45.96
1-22'	22	$4.50	$99.00
Top of wall angle block 10/12 pitch			
6-12'	72	$3.52	$253.44
starter block 7/8x4			
120 lf	120	$0.50	$60.00
2016 square feet of 1x8 T&G white pine for Ceiling and Soffits	2016	$1.10	$2,217.60
4 - Pails of 12" log screws (250 each)	4	$200.00	$800.00
1 - box of 16" log screws (250 each)	1	$255.00	$255.00
200 - 250' rolls of 3/8"w x 3/8"h foam tape for two strips each course	200	$4.18	$836.00
		TOTAL	$24,821.80